



915-006.019

Practitioner Docket No. _____

PATENT

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

In re application of: G. SIVARAMAN et al. Group No.: 2155
Application No.: 0 10 / 608,889
Filed: June 27, 2003 Examiner: To Be Assigned
For: Method and Device for Retrieving Data Store Access Information


Assistant Commissioner for Patents
Washington, D.C. 20231

TRANSMITTAL OF CERTIFIED COPY

Attached please find the certified copy of the foreign application from which priority is claimed for this case:

Country: International/WIPO
Application Number: PCT/IB02/02523
Filing Date: June 28, 2002

WARNING: "When a document that is required by statute to be certified must be filed, a copy, including a photocopy or facsimile transmission of the certification is not acceptable." 37 C.F.R. § 1.4(f) (emphasis added).


SIGNATURE OF PRACTITIONER

Reg. No. 27,550

Alfred A. Fressola

(type or print name of practitioner)

Tel. No. (203) 261-1234

Ware, Fressola, Van Der Sluys & Adolphson LLP

P.O. Address Bradford Green, Building Five
755 Main Street, P.O. Box 224
Monroe, CT 06468

Customer No.: 004955

NOTE: The claim to priority need be in no special form and may be made by the attorney or agent, if the foreign application is referred to in the oath or declaration, as required by § 1.63.

CERTIFICATE OF MAILING (37 C.F.R. § 1.8a)

I hereby certify that this correspondence is, on the date shown below is being deposited with the United States Postal Service with sufficient postage as first class mail in an envelope addressed to the Assistant Commissioner for Patents, Washington, D.C. 20231.


Signature

Date: December 16, 2003

Annemarie Maher

(type or print name of person certifying)

(Transmittal of Certified Copy [5-4])



**WORLD INTELLECTUAL PROPERTY ORGANIZATION
ORGANISATION MONDIALE DE LA PROPRIÉTÉ INTELLECTUELLE**

34, chemin des Colombettes, Case postale 18, CH-1211 Genève 20 (Suisse)
Téléphone: (41 22) 338 91 11 - e-mail: wipo.mail @ wipo.int. - Fac-similé: (41 22) 733 54 28

**PATENT COOPERATION TREATY (PCT)
TRAITÉ DE COOPÉRATION EN MATIÈRE DE BREVETS (PCT)**

**CERTIFIED COPY OF THE INTERNATIONAL APPLICATION AS FILED
AND OF ANY CORRECTIONS THERETO**

**COPIE CERTIFIÉE CONFORME DE LA DEMANDE INTERNATIONALE, TELLE QU'ELLE
A ÉTÉ DÉPOSÉE, AINSI QUE DE TOUTES CORRECTIONS Y RELATIVES**

International Application No. }
Demande internationale n° } **PCT/IB02/02523**


International Filing Date }
Date du dépôt international } **28 June 2002**
(28.06.02)

Geneva/Genève,

06 June 2003
(06.06.03)

**International Bureau of the
World Intellectual Property Organization (WIPO)**

**Bureau International de l'Organisation Mondiale
de la Propriété Intellectuelle (OMPI)**



J.-L. Baron

**Head, PCT Receiving Office Section
Chef de la section "office récepteur du PCT"**

PCT

REQUEST

The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty.

For receiving Office use only

PCT / IB 0 2 / 0 2 5 2 3
International Application No.

28 JUNE 2002 (28.06.02)
International Filing Date

INTERNATIONAL BUREAU OF WIPO

PCT International Application

Name of receiving Office and "PCT International Application"

Applicant's or agent's file reference
(if desired) (12 characters maximum) 51069 WO

B x No. I TITLE OF INVENTION

Method and device for retrieving data store access information

Box No. II APPLICANT

☐ This person is also inventor

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

Nokia Corporation
Keilalahdentie 4
02150 Espoo
Finland

Telephone No.

Facsimile No.

Teleprinter No.

Applicant's registration No. with the Office

State (that is, country) of nationality:

FI

State (that is, country) of residence:

FI

This person is applicant
for the purposes of:

☐ all designated States☒ all designated States except the United States of America☐ the United States of America only☐ the States indicated in the Supplemental Box

Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

SIVARAMAN, Ganesh
Avaruuskatu 4 C, 50
02210 Espoo
Finland

This person is:

☐ applicant only☒ applicant and inventor☐ inventor only (If this check-box is marked, do not fill in below.)

Applicant's registration No. with the Office

State (that is, country) of nationality:

IN

State (that is, country) of residence:

FI

This person is applicant
for the purposes of:

☐ all designated States☐ all designated States except the United States of America☒ the United States of America only☐ the States indicated in the Supplemental Box☒ Further applicants and/or (further) inventors are indicated on a continuation sheet.

Box No. IV AGENT OR COMMON REPRESENTATIVE; OR ADDRESS FOR CORRESPONDENCE

The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as:

☒ agent☐ common representative

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)

KURIG, Thomas
Becker, Kurig, Straus
Bavariastr. 7
80336 München
Germany

Telephone No.

089-746 303 0

Facsimile No.

089-746 303 11

Teleprinter No.

Agent's registration No. with the Office

☐ Address for correspondence: Mark this check-box where no agent or common representative is/has been appointed and the space above is used instead to indicate a special address to which correspondence should be sent.

CONFIRMATION COPY

Continuation of Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)*If none of the following sub-boxes is used, this sheet should not be included in the request.*

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

METTÄLÄ, Riku
Dunckerinkatu 1 B 6
33580 Tampere
Finland

This person is:

- ☐ applicant only
☒ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below.)

Applicant's registration No. with the Office

State (that is, country) of nationality:

FI

State (that is, country) of residence:

FI

This person is applicant for the purposes of:

☐ all designated States☐ all designated States except the United States of America☒ the United States of America only☐ the States indicated in the Supplemental Box

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

PIISPANEN, Jussi
Vastarannankatu 27 D 14
33610 Tampere
Finland

This person is:

- ☐ applicant only
☒ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below.)

Applicant's registration No. with the Office

State (that is, country) of nationality:

FI

State (that is, country) of residence:

FI

This person is applicant for the purposes of:

☐ all designated States☐ all designated States except the United States of America☒ the United States of America only☐ the States indicated in the Supplemental Box

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

This person is:

- ☐ applicant only
☐ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below.)

Applicant's registration No. with the Office

State (that is, country) of nationality:

State (that is, country) of residence:

This person is applicant for the purposes of:

☐ all designated States☐ all designated States except the United States of America☐ the United States of America only☐ the States indicated in the Supplemental Box

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

This person is:

- ☐ applicant only
☐ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below.)

Applicant's registration No. with the Office

State (that is, country) of nationality:

State (that is, country) of residence:

This person is applicant for the purposes of:

☐ all designated States☐ all designated States except the United States of America☐ the United States of America only☐ the States indicated in the Supplemental Box

☐ Further applicants and/or (further) inventors are indicated on another continuation sheet.

Box No. V DESIGNATION OF STATES

Mark the applicable check-boxes below; at least one must be marked.

The following designations are hereby made under Rule 4.9(a):

Regional Patent

- ☒ **AP ARIPO Patent:** GH Ghana, GM Gambia, KE Kenya, LS Lesotho, MW Malawi, MZ Mozambique, SD Sudan, SL Sierra Leone, SZ Swaziland, TZ United Republic of Tanzania, UG Uganda, ZM Zambia, ZW Zimbabwe, and any other State which is a Contracting State of the Harare Protocol and of the PCT (if other kind of protection or treatment desired, specify on dotted line)
- ☒ **EA Eurasian Patent:** AM Armenia, AZ Azerbaijan, BY Belarus, KG Kyrgyzstan, KZ Kazakhstan, MD Republic of Moldova, RU Russian Federation, TJ Tajikistan, TM Turkmenistan, and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT
- ☒ **EP European Patent:** AT Austria, BE Belgium, CH & LI Switzerland and Liechtenstein, CY Cyprus, DE Germany, DK Denmark, ES Spain, FI Finland, FR France, GB United Kingdom, GR Greece, IE Ireland, IT Italy, LU Luxembourg, MC Monaco, NL Netherlands, PT Portugal, SE Sweden, TR Turkey, and any other State which is a Contracting State of the European Patent Convention and of the PCT
- ☒ **OA OAPI Patent:** BF Burkina Faso, BJ Benin, CF Central African Republic, CG Congo, CI Côte d'Ivoire, CM Cameroon, GA Gabon, GN Guinea, GQ Equatorial Guinea, GW Guinea-Bissau, ML Mali, MR Mauritania, NE Niger, SN Senegal, TD Chad, TG Togo, and any other State which is a member State of OAPI and a Contracting State of the PCT (if other kind of protection or treatment desired, specify on dotted line)

National Patent (if other kind of protection or treatment desired, specify on dotted line):

- | | | |
|---|--|--|
| <input checked="" type="checkbox"/> AE United Arab Emirates | <input checked="" type="checkbox"/> GM Gambia | <input checked="" type="checkbox"/> NZ New Zealand |
| <input checked="" type="checkbox"/> AG Antigua and Barbuda | <input checked="" type="checkbox"/> HR Croatia | <input checked="" type="checkbox"/> OM Oman |
| <input checked="" type="checkbox"/> AL Albania | <input checked="" type="checkbox"/> HU Hungary | <input checked="" type="checkbox"/> PH Philippines |
| <input checked="" type="checkbox"/> AM Armenia | <input checked="" type="checkbox"/> ID Indonesia | <input checked="" type="checkbox"/> PL Poland |
| <input checked="" type="checkbox"/> AT Austria | <input checked="" type="checkbox"/> IL Israel | <input checked="" type="checkbox"/> PT Portugal |
| <input checked="" type="checkbox"/> AU Australia | <input checked="" type="checkbox"/> IN India | <input checked="" type="checkbox"/> RO Romania |
| <input checked="" type="checkbox"/> AZ Azerbaijan | <input checked="" type="checkbox"/> IS Iceland | <input checked="" type="checkbox"/> RU Russian Federation |
| <input checked="" type="checkbox"/> BA Bosnia and Herzegovina | <input checked="" type="checkbox"/> JP Japan | |
| <input checked="" type="checkbox"/> BB Barbados | <input checked="" type="checkbox"/> KE Kenya | <input checked="" type="checkbox"/> SD Sudan |
| <input checked="" type="checkbox"/> BG Bulgaria | <input checked="" type="checkbox"/> KG Kyrgyzstan | <input checked="" type="checkbox"/> SE Sweden |
| <input checked="" type="checkbox"/> BR Brazil | <input checked="" type="checkbox"/> KP Democratic People's Republic of Korea | <input checked="" type="checkbox"/> SG Singapore |
| <input checked="" type="checkbox"/> BY Belarus | <input checked="" type="checkbox"/> KR Republic of Korea | <input checked="" type="checkbox"/> SI Slovenia |
| <input checked="" type="checkbox"/> BZ Belize | <input checked="" type="checkbox"/> KZ Kazakhstan | <input checked="" type="checkbox"/> SK Slovakia |
| <input checked="" type="checkbox"/> CA Canada | <input checked="" type="checkbox"/> LC Saint Lucia | <input checked="" type="checkbox"/> SL Sierra Leone |
| <input checked="" type="checkbox"/> CH & LI Switzerland and Liechtenstein | <input checked="" type="checkbox"/> LK Sri Lanka | <input checked="" type="checkbox"/> TJ Tajikistan |
| <input checked="" type="checkbox"/> CN China | <input checked="" type="checkbox"/> LR Liberia | <input checked="" type="checkbox"/> TM Turkmenistan |
| <input checked="" type="checkbox"/> CO Colombia | <input checked="" type="checkbox"/> LS Lesotho | <input checked="" type="checkbox"/> TN Tunisia |
| <input checked="" type="checkbox"/> CR Costa Rica | <input checked="" type="checkbox"/> LT Lithuania | <input checked="" type="checkbox"/> TR Turkey |
| <input checked="" type="checkbox"/> CU Cuba | <input checked="" type="checkbox"/> LU Luxembourg | <input checked="" type="checkbox"/> TT Trinidad and Tobago |
| <input checked="" type="checkbox"/> CZ Czech Republic | <input checked="" type="checkbox"/> LV Latvia | |
| <input checked="" type="checkbox"/> DE Germany | <input checked="" type="checkbox"/> MA Morocco | <input checked="" type="checkbox"/> TZ United Republic of Tanzania |
| <input checked="" type="checkbox"/> DK Denmark | <input checked="" type="checkbox"/> MD Republic of Moldova | <input checked="" type="checkbox"/> UA Ukraine |
| <input checked="" type="checkbox"/> DM Dominica | | <input checked="" type="checkbox"/> UG Uganda |
| <input checked="" type="checkbox"/> DZ Algeria | | <input checked="" type="checkbox"/> US United States of America |
| <input checked="" type="checkbox"/> EC Ecuador | <input checked="" type="checkbox"/> MG Madagascar | |
| <input checked="" type="checkbox"/> EE Estonia | <input checked="" type="checkbox"/> MK The former Yugoslav Republic of Macedonia | <input checked="" type="checkbox"/> UZ Uzbekistan |
| <input checked="" type="checkbox"/> ES Spain | <input checked="" type="checkbox"/> MN Mongolia | <input checked="" type="checkbox"/> VN Viet Nam |
| <input checked="" type="checkbox"/> FI Finland | <input checked="" type="checkbox"/> MW Malawi | <input checked="" type="checkbox"/> YU Yugoslavia |
| <input checked="" type="checkbox"/> GB United Kingdom | <input checked="" type="checkbox"/> MX Mexico | <input checked="" type="checkbox"/> ZA South Africa |
| <input checked="" type="checkbox"/> GD Grenada | <input checked="" type="checkbox"/> MZ Mozambique | <input checked="" type="checkbox"/> ZM Zambia |
| <input checked="" type="checkbox"/> GE Georgia | <input checked="" type="checkbox"/> NO Norway | <input checked="" type="checkbox"/> ZW Zimbabwe |
| <input checked="" type="checkbox"/> GH Ghana | | |

Check-boxes below reserved for designating States which have become party to the PCT after issuance of this sheet:

- | | | |
|--------------------------------|--------------------------------|--------------------------------|
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |

Precautionary Designation Statement: In addition to the designations made above, the applicant also makes under Rule 4.9(b) all other designations which would be permitted under the PCT except any designation(s) indicated in the Supplemental Box as being excluded from the scope of this statement. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit. (Confirmation (including fees) must reach the receiving Office within the 15-month time limit.)

Box No. VI PRIORITY CLAIM

The priority of the following earlier application(s) is hereby claimed:

Filing date of earlier application (day/month/year)	Number of earlier application	Where earlier application is:		
		national application: country	regional application:* regional Office	international application: receiving Office
item (1)				
item (2)				
item (3)				
item (4)				
item (5)				

☐ Further priority claims are indicated in the Supplemental Box.

The receiving Office is requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) (*only if the earlier application was filed with the Office which for the purposes of this international application is the receiving Office*) identified above as:

☐ all items
 ☐ item (1)
 ☐ item (2)
 ☐ item (3)
 ☐ item (4)
 ☐ item (5)
 ☐ other, see Supplemental Box

* Where the earlier application is an ARIPO application, indicate at least one country party to the Paris Convention for the Protection of Industrial Property or one Member of the World Trade Organization for which that earlier application was filed (Rule 4.10(b)(ii)):

Box No. VII INTERNATIONAL SEARCHING AUTHORITY

Choice of International Searching Authority (ISA) (if two or more International Searching Authorities are competent to carry out the international search, indicate the Authority chosen; the two-letter code may be used):

ISA / .SE.

Request to use results of earlier search; reference to that search (if an earlier search has been carried out by or requested from the International Searching Authority):

Date (day/month/year) Number Country (or regional Office)

Box No. VIII DECLARATIONS

The following **declarations** are contained in Boxes Nos. VIII (i) to (v) (mark the applicable check-boxes below and indicate in the right column the number of each type of declaration):

Number of
declarations

- | | | |
|---|--|---|
| <input type="checkbox"/> Box No. VIII (i) | Declaration as to the identity of the inventor | : |
| <input type="checkbox"/> Box No. VIII (ii) | Declaration as to the applicant's entitlement, as at the international filing date, to apply for and be granted a patent | : |
| <input type="checkbox"/> Box No. VIII (iii) | Declaration as to the applicant's entitlement, as at the international filing date, to claim the priority of the earlier application | : |
| <input type="checkbox"/> Box No. VIII (iv) | Declaration of inventorship (only for the purposes of the designation of the United States of America) | : |
| <input type="checkbox"/> Box No. VIII (v) | Declaration as to non-prejudicial disclosures or exceptions to lack of novelty | : |

Box No. IX CHECK LIST; LANGUAGE OF FILING

This international application contains:

(a) the following number of sheets in paper form:

request (including declaration sheets) : 5
 description (excluding sequence listing part) : 22
 claims : 4
 abstract : 1
 drawings : 6

Sub-total number of sheets : 38

sequence listing part of description (actual number of sheets if filed in paper form, whether or not also filed in computer readable form; see (b) below) :

Total number of sheets :

(b) sequence listing part of description filed in computer readable form

(i) ☐ only (under Section 801(a)(i))(ii) ☐ in addition to being filed in paper form (under Section 801(a)(ii))

Type and number of carriers (diskette, CD-ROM, CD-R or other) on which the sequence listing part is contained (additional copies to be indicated under item 9(ii), in right column):

This international application is accompanied by the following item(s) (mark the applicable check-boxes below and indicate in right column the number of each item):

1. ☒ fee calculation sheet : 1
 2. ☐ original separate power of attorney :
 3. ☐ original general power of attorney :
 4. ☐ copy of general power of attorney; reference number, if any: :
 5. ☐ statement explaining lack of signature :
 6. ☐ priority document(s) identified in Box No. VI as item(s): :
 7. ☐ translation of international application into (language): :
 8. ☐ separate indications concerning deposited microorganism or other biological material :
 9. ☐ sequence listing in computer readable form (indicate also type and number of carriers (diskette, CD-ROM, CD-R or other)) :
 (i) ☐ copy submitted for the purposes of international search under Rule 13ter only (and not as part of the international application) :
 (ii) ☐ (only where check-box (b)(i) or (b)(ii) is marked in left column) additional copies including, where applicable, the copy for the purposes of international search under Rule 13ter :
 (iii) ☐ together with relevant statement as to the identity of the copy or copies with the sequence listing part mentioned in left column :
 10. ☐ other (specify): :

Number of items

Figure of the drawings which should accompany the abstract: Fig. 2

Language of filing of the international application: English

Box No. X SIGNATURE OF APPLICANT, AGENT OR COMMON REPRESENTATIVE

Next to each signature, indicate the name of the person signing and the capacity in which the person signs (if such capacity is not obvious from reading the request).

Munich, June 28, 2002



Dr. Thomas Kurig - European Patent Attorney -

For receiving Office use only

1. Date of actual receipt of the purported international application:

28 JUNE 2002 (28.06.02)

3. Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application:

4. Date of timely receipt of the required corrections under PCT Article 11(2):

5. International Searching Authority (if two or more are competent):

ISA / SE

6. ☒ Transmittal of search copy delayed until search fee is paid

2. Drawings:

☐ received:☐ not received:

For International Bureau use only

Date of receipt of the record copy by the International Bureau:

Assignee: Nokia Corporation
Our Ref.: 51069 WO (KG/TP)
Your Ref.: NC 35778

Method and device for retrieving data store access information

5 The present invention relates to a method and a device for requesting information relating to data stores and to a method and a device for returning data store information in response to a request, respectively. Particularly, the present invention relates to requesting of information relating to data stores to be identified in accordance with data store descriptors relating to properties of the data stores or properties of the data stored in said data stores.

10 The synchronization of data is a well known concept or technique for users, respectively, having a at least two different electronic device in use and processing the same kind of data with these electronic devices. In general, synchronization takes place between a terminal device (e.g., a mobile phone) and a server device (e.g., an application in a local PC or a dedicated synchronization server). Data of terminals, such as portable computers, PDA terminals (personal
15 digital assistant), mobile stations or pagers, can be synchronized with network applications, applications of desktop computers or with other data stores of the telecommunications system, wherein the term data store should be understood as broad as possible, i.e. shall cover arbitrary sets of data. In particular, data of calendar and e-mail applications are typically synchronized.

20 Synchronization has been based on the use of different manufacturer-specific protocols which are incompatible. This restricts the use of terminal or data types and often causes troubles to the user. In mobile communication, in particular, it is important that data can be retrieved and updated regardless of the terminal and application used.

25 To improve synchronization of application data, a language known and referred to as synchronization markup language SyncML has been designed, which is based on the extensible markup language (XML). By using a SyncML synchronization protocol, which employs messages in the SyncML format, data of any application can be synchronized between networked terminals and a network server of any kind. The SyncML synchronization protocol works both in
30 wireless and in fixed networks and supports several transmission protocols. The above presented SyncML synchronization technology addresses preferably the synchronization of data stores or databases, respectively.

35 The SyncML synchronization technology offers an flexible and effective method to update data store contents relating to different applications, i.e. a substantially automated method, in case that

the first configuration of the synchronization required details has been managed. With reference to the SyncML synchronization, SyncML for example mandates alerting of the data stores that need to be synchronized. To alert the data stores, information, such as addresses of data stores (uniform resource identifier URI), type of the content stored by the data store, about the data stores is required. Currently this information is either entered by the user or sent as an over-the-air setting. For a user to enter the data store information, it is necessary to know both the client-side device and server-side device data stores. This is definitely cumbersome for the user when considering the possible numbers of data stores a single user may have on the client and/or server device.

Up to now, the required details are either manually entered by the user or in case of a terminal device having cellular phone communication capabilities they are transmitted as an over-the-air setting. As mentioned above, the manual entering of details is quite a not trivial undertaking and the user may face several problems and also contradicts an easy usability of terminals offering such a synchronization service.

Mobile communication service providers are aware that ordinary users are not familiar to or experienced in configuring one or more applications of a mobile phone, especially in view of the fact that the number of applications to be configured rises permanently and the user efforts required for proper configuring become more and more complicate due to the improvement of functions provided by the one or more application. Hence, a procedure has been introduced allowing to configure a mobile phone via the air interface, i.e. the over-the-air (OTA) setting procedure. The over-the-air setting is based on the short message service (SMS) provided among others in global systems for mobile communication (GSM). By the means of over-the-air setting a broad number of different setting can be managed. An over-the-air setting may contain address and property information about a data store of a server for configuring an application associated to the type of data provided for access by this data store. Such an over-the-air setting is received by a mobile phone and results that the information coded in the over-the-air setting is employed as a default configuration of the application to be configured. Individual configuration which includes for example the configuring of several data stores for one application is not possible by the means of an over-the-air setting. Nonetheless more restricting is the fact that *only* cellular mobile communication devices support the over-the-air setting while -of course- synchronization technology is supported by any networking devices not having necessarily the capability to communicate via cellular communication networks.

The above mentioned introduction has been presented with reference to the SyncML synchronization. But the provision of detailed information relating to a networked service is

more common. The growing interlinking of networking devices by the means of wire-base and wireless communication networks and the employment of services provided centrally to a plurality of devices accessing the service causes and results in a growing configuration effort comprising the detailed defining information relating to the networked service to be properly established. A networked service shall be understood as broad as possible. For example, the networked service is provided by a network server accessible via known networks. Further, the networked service is for example also provided by a notebook, laptop, desktop etc. computer provided only to a locally connected electronic device such as a mobile phone, mobile handheld, personal digital assistant, further mobile computer etc. The networked service can be provided exclusively to only one participating or locally participating counterpart device.

The object of the invention is to provide at least one method which overcomes the above state of the art problems underlying no specific restrictions. The object of the invention is achieved with a method for generating a data store retrieval request instructing, e.g. a remote device, to transmit information relating to and retrieved from identified data store(s), a method for generating a corresponding response comprising retrieved information relating to the identified data store(s), corresponding devices adapted to perform these methods, computer programs and software tools which are disclosed in the independent claims. Additional embodiments of the invention are disclosed in the dependent claims.

According to an embodiment of the invention, a method for generating a request by a first device, e.g. a user terminal device, to obtain information relating to at least one data store is provided. The request is to be transmitted to a second device, e.g. a remote device (remote terminal device) or server device, respectively, to be processed in accordance with instructions comprised in the request. In order to clarify operations of both the first device and the second device, the first device will be termed abstractly as requesting device or request generating device whereas the second device will be termed abstractly as request receiving device or response generating device, respectively. The data store of which information is to be retrieved is accessible via a communication network by the requesting device (first device). The request is generated by including at least one data store descriptor and a command representation. The including of the at least one data store descriptor and a command representation may involve a coding of both, i.e. the command representation is for example a coding sequence containing one or more coding terms (instructions) all dedicated to the instructional purpose in accordance to the intention of the request according to an embodiment of the present invention. The data store descriptor is a sequence adapted to allow an identification or a characterization of at least one matching data store. Further, the including may be understood as an appending, an adding etc. The command instructs the request receiving device (second device) to identify at least one data store in

accordance with the at least one data store descriptor and to retrieve information relating to said at least one identified data store. This retrieved information are to be coded in a response in order to re-transmit the retrieved information to the requesting device (first device), wherein the retrieved information are adapted to configure at least one application executed on the requesting device (first device) to enable the configured application to access the at least one identified data store, i.e. to retrieve data from the data store, to store data in the data store, to modify data of the data store, or to apply common synchronization functions, etc.

According to an embodiment of the invention, the generating of the request further comprises an identification of the at least one data store descriptor. The identification can be a retrieving of the data store descriptor from the applications to be configured. The identification can be an entering of the one or more data store descriptors by a user. Moreover, the device generating the above described request can maintain a list or database, respectively, containing information about data store descriptors and information about assignments of the data store descriptors to applications executable on the request generating device.

According to an embodiment of the invention, one or more data store descriptors to be coded in the request are one or more descriptors of data store content types. A data store content type relates to a content type of data store dedicated to store data of a certain content type such that the storing data store is identifiable by the data store content type. According to an embodiment of the invention, one or more data store descriptors coded in the request represent one or more data content types of the one or more data stores.

According to an embodiment of the invention, the data type descriptor is a MIME (multipurpose internet mail extension) content type definition. The MIME type was originally introduced to describe the content of attachments of emails. Nowadays, the MIME type definition is extended to several networked services to define content of data exchanged in-between of networked applications to ensure the transferring of the data to an adequate application enabled to process the data. The MIME content type definition comprises a type and a subtype definition separated by a separator. Moreover, the device generating the above described request can maintain a list or database, respectively, containing information about data type descriptors, i.e. the MIME type, and information about assignments of the data type descriptors to applications executable on the request generating device.

According to an embodiment of the invention, the information relating to the at least one data store includes an address information necessary to enable applications of the requesting device (first device) to get access to the one or more identified data store.

According to an embodiment of the invention, the request is based on the synchronization markup language (SyncML) protocol.

5 According to an embodiment of the invention, the command of the request is a special ALERT command. An alert command specified in SyncML is a command to convey notification related information such as data synchronization request to the receiving device and thus it provides a mechanism for communicating content information, such as state information or notifications to an application on the receiving device. The ALERT command comprises an ALERT CODE
10 instructing the aforementioned operations, i.e. instructing to initiate a data store retrieval process comprising a characterizing or identifying of at least one data store by means of the at least one descriptor. Therefore, the ALERT command further includes a META element containing a TYPE element for defining the at least one descriptor. Additionally, the request includes several ALERT commands each including the aforementioned elements and each including one
15 descriptor. The number of ALERT commands corresponds to the number of descriptor.

According to an embodiment of the invention, a method for generating a response containing information relating to at least one data store is provided. The generation of the response is initiated upon receiving a request for information relating to the at least one data store from a
20 requesting device (first device) via a communication network. The method comprises identifying at least one data store in accordance with at least one data store descriptor included in said received request and retrieving information relating to the at least one identified data store from the at least one identified data store and/or generating information about the data store matching and identifying process. In particular, the identifying of at least one data store in accordance with
25 at least one data store descriptor results in an matching result representing at least one matching (i.e. identified or successfully) data store or representing information about non-matching (i.e. non-identified or unsuccessfully) result. In case at least one identified data store is successfully matched and identified the information relating to the at least one identified data store is retrieved from at least one identified data store as mentioned above, whereas in case of an non-
30 matching result (i.e. an unsuccessfully matching or identifying) the information relating to the at least one identified data store comprises information for informing the requesting device (first device) about the non-matching result, i.e. an exception response. The information relating to the at least one successfully and/or unsuccessfully identified data store /data store descriptors is included into the response. The including of the retrieved information into the response may
35 involve a coding of the retrieved information to an instructional sequence expressing the retrieved information in a corresponding expression or instructional sequence adapted to be parsed by the requesting device. Such an instructional sequence may comprise one or more

coding terms (instructions) all dedicated to the instructional purpose in accordance to the intention of the response according to an embodiment of the present invention. Further, the including may be understood as an appending, an adding etc. The generated response is finally transmitted to the requesting device (first device). The response comprised information relating to said at least one identified data store is further employed for configuring an application executed on the requesting device (first device) for enabling access to the at least one identified data store, wherein said retrieved information relating to said at least one data store are employed to configure at least one application executed on said requesting device (first device) to enable access to said at least one identified data store via a communication network.

According to an embodiment of the invention, the request is a request according to the aforementioned method for generating a request by a requesting device (first device) to retrieve information relating to at least one data store.

According to an embodiment of the invention, one or more data store descriptors coded in the request represent one or more data content types of the one or more data stores. According to an embodiment of the invention, one or more data store descriptors coded in the request are one or more data store content types.

According to an embodiment of the invention, the information relating to the at least one data store includes at least one address information. The address information provides an application executed on the requesting device (first device) to access the at least one data store.

According to an embodiment of the invention, the response is based on the synchronization markup language (SyncML) protocol.

According to an embodiment of the invention, the response includes at least one STATUS element. This element further includes a SOURCE element containing at least one address information of the at least one identified data store. Additionally, the response includes several STATUS elements each including an address information of one identified data store. The at least address information is coded by the means of a uniform resource identifier (URI), a uniform resource name (URN) or a combination of both the uniform resource identifier (URI) and the uniform resource name (URN).

According to an embodiment of the invention, a software tool for handling data store related information is provided. The software tool comprises program portions for carrying out the

operations of the aforementioned methods when the software tool is implemented in a computer program and/or executed.

5 According to an embodiment of the invention, there is provided a computer program for handling data store related information. The computer program comprises program code portions for carrying out the operations of the aforementioned methods when the program is executed on a processing device, a computer or a network device.

10 According to an embodiment of the invention, a computer program product is provided which comprises program code portions stored on a computer readable medium for carrying out the aforementioned methods when said program product is executed on a processing device, a computer or network device.

15 According to an embodiment of the invention a device is provided for generating a request to retrieve information relating to at least one data store. The device includes at least a request generating component for generating the request and a network interface for transmitting the request to a request receiving device (second device) and for accessing the at least one data store via a communication network. Further, the request generating component comprises additionally a component for including at least one data store descriptor to be included in the request and a
20 component for including a command to be included in the request. The component for including the descriptor and/or the command may comprise coding ability to generate a corresponding instructional sequence as mentioned above. Further, the including functionality of the corresponding component may be understood as an appending, an adding etc. functionality. The command instructs the request receiving device (second device) to identify at least one data store
25 in accordance with the at least one data store descriptor, to retrieve information relating to said at least one identified data store and to return the retrieved information. Additionally, the network interface is a network interface able to transmit the request via a communication network and further to receive the instructed response. In order to decode and operate in accordance with the received response, the device also includes a parser adapted to analyze the response and to
30 transmit extracted information relating to the identified data store to the applications requiring the extracted information or to a configuring component responsible to take account of the extracted information.

35 According to an embodiment of the invention, the device for generating a request is adapted to perform the aforementioned methods according to an embodiment of the invention.

According to an embodiment of the invention a device for generating a response containing

information relating to at least one data store in consequence to receiving a request for information of the at least one data store from a requesting device (first device). Therefor the device comprises a network interface for receiving the request and for transmitting the response via a communication network and a response generating component for generating the response.

5 Further the device comprises a component for identifying at least one data store in accordance with at least one data store descriptor included in the received request, a component for retrieving information relating to the at least one identified data store form the at least one identified data store and a component for including the retrieved information relating to the at least one identified data store. The component for including is comprised in the response generating
10 component. The component for including comprise coding ability to generate a corresponding instructional sequence as mentioned above. Further, the including functionality of the corresponding component may be understood as an appending, an adding etc. functionality. The described device comprises additionally a parser able to analyze the received request and initiate the necessary operations in accordance with the coded instructions relating to the aforementioned
15 method, wherein the initiating of necessary operations is an activating of the described components adapted to operate in accordance with the coded instructions.

According to an embodiment of the invention, the device for generating a response is adapted to perform the aforementioned methods according to an embodiment of the invention.

20 It invention will be described in greater detail by means of embodiments with reference to the accompanying drawings, in which

Fig. 1 shows a schematic diagram illustrating a set of exemplary electronic device
25 between which synchronization of information can be operated;

Fig. 2 shows a flow diagram illustrating an operational sequence for generating a request according to an embodiment of the invention;

Fig. 3 shows a flow diagram illustrating an operational sequence for generating a response in reaction to a request, e.g. as illustrated in Fig. 1, according to an
30 embodiment of the invention;

Fig. 4 shows a request based on a modified XML-coding in accordance with the SyncML synchronization standard according to an embodiment of the invention;

Fig. 5 shows a response based on a modified XML-coding in accordance with the
35 SyncML synchronization standard according to an embodiment of the invention; and

Fig. 6 shows a block diagram illustrating components of a client device and a server device for synchronization according to an embodiment of the invention.

In the following, the embodiments of the invention will be described in a system supporting the SyncML synchronization standard without limiting the invention thereto. Information relating to the SyncML standard can be obtained from the SyncML Initiative providing publicly the full standard documentation. Same or equal parts, features and/or operations shown in the figures will be referred to using the same reference numerals.

Fig. 1 shows a schematic diagram illustrating a set of exemplary electronic device between which synchronization of information can be operated. A certain data store content of preferably mobile terminals shall be harmonized with data store content provided by designated devices. Conventionally, mobile terminals act as synchronization clients harmonizing or synchronizing certain pre-defined data with the contents of a data store or several data stores provided by dedicated server devices. Fig. 1 illustrates a plurality of possible client devices and server devices for the synchronization operation. Typically, client devices are mobile stations like mobile phones 17 or personal digital assistants (PDA), mobile computers like notebooks 15, digital cameras 16 or personal computers (PC). Further, dedicated synchronization server devices may be desktop computers like a personal computer 10, a dedicated network server 11 or even a mobile computer like a notebook 12. It shall be noted that the client device functionality is not limited to mobile terminals as described above although the presented concept of synchronization is described in view of mobile terminals connected to dedicated serving devices.

A corresponding synchronization process in accordance with the SyncML protocol standard is established via an appropriate logical communication connection. The logical communication connection is provided by any communication networks in combination with transport protocols to which the synchronization protocol is adapted. A suitable communication network may be a local area network (LAN) or a wide area network (WAN) which may comprise the internet and an intranet of a company but also wire-based serial networks such as universal serial bus (USB) or standardized serial communication (e.g. RS-232). The participating synchronization devices may be also connected via a wireless communication network such as a mobile network supporting global system for mobile communication (GSM) services and/or supporting general packet radio services (GPRS), a third generation mobile communication network such as a universal mobile telecommunication system (UMTS) network, a wireless local area network (WLAN), short range radio communication network, such as a Bluetooth network, wireless local loop (WLL) or an infrared network (IrDA). The logical communication connection between the participating synchronization devices may be provided by a single communication network of the

aforementioned type but also may be provided by several communication networks of the aforementioned types interconnected by dedicated network routing devices.

With respect to the SyncML protocol standard the SyncML synchronization protocol and hence also with respect to the SyncML device management protocol standard the SyncML device management protocol is implemented on the top of appropriate protocols in accordance with the type of employed communication network. Appropriate protocols on which top the SyncML synchronization protocol can be implemented are the hyper text transfer protocol (HTTP), the wireless session protocol (WSP) of the wireless application protocol (WAP) standard, the object exchange protocol (OBEX) used for cable connections, such as universal serial bus (USB) or RS-232, for short-range radio frequency connections (Bluetooth) or for infrared connections (IrDA), the transport control protocol/internet protocol (TCP/IP) stack and on top of the transport layer service which is offered by the e-mail protocol (e.g. simple mail transfer protocol, SMTP).

Transfer at the lower layer can be performed according to the underlying network using e.g. short messages SMS (short message service) or other signaling type transmission methods (e.g. USSD; unstructured supplementary service data), circuit-switched data calls, packet-switched data transfer services as well as paging message service, messages provided via cell broadcast and the like.

In the following the term data store shall be understood as broad as possible, i.e. shall cover arbitrary set(s) of data provided by data storage(s) to be accessed. In particular, the sets of data relate to specific applications and may be organized to meet application specific requirements such as data of calendar applications, directory applications, e-mail applications and the like. Further, the arbitrary set(s) of data can be organized in one or more databases including data records providing data to be access. Further the term data store shall be understood as covering network data services or networked service, respectively, i.e. shall cover arbitrary set(s) of data provided by networked service(s) to be accessed in similar to data store(s). Conventionally, networks services are based on data stores having a specific service related data store content.

The following flow diagrams depict operational sequences according to embodiments of the methods of the present invention. The depicted sequences of operations are just illustrative and not limiting thereto. Further realizations based on similar or related operational sequences are also possible.

Fig. 2 illustrates an operational sequence for generating a request according to an embodiment of the invention.

In an operation S100, the data store retrieval process is initiated. Particularly, the data store retrieval process relates to a retrieval of information relating to data stores, wherein the retrieval process is based on descriptions of the data stores, the data store content and/or the data stored/provided by the data store. In the following such a data store description specific to a certain data store or certain data stores will be termed as descriptor.

The kind of employed descriptor depends on the kind of data store and the kind of data stored in the data store but depends also on one or several applications accessing and/or processing data of the data stores. A valid descriptor comprises information which allows to identify a corresponding data store to be retrieved but also to identify a plurality of corresponding data stores since data may be distributed among data stores or may be made available via several data stores. Further, a physical data store can be divided into several logically different and independent data stores such that a valid data store description corresponds to a plurality of logical data stores appearing to be different.

An information relating to the data store comprises information allowing to access the data store, such as at least an address information but also information relating to access requirements and/or access limitations and the like, i.e. information required for accessing the data store. It shall be noted that the term access to a data store shall cover all possible and/or allowed handling of data stored in the data store. The handling of data is to be understood as a storing of data in the data store, a retrieval of data from the data store, a modifying of data stored in the data store, a deleting of data stored in the data store and further data manipulating processes.

The following description of the illustrated operational sequence is based on the assumption that a requesting device requests information relating to data stores provided by a data serving device. The requested information relating to the data stores shall put the requesting device itself into the situation to access the data stores of the serving device in subsequent processes. Therefore, the requesting device executes at least one application capable to access or requiring access to one or more data stores provided by the data serving device. The at least one application has to be informed about the way to access the data store and further necessary information relating the data store and the data provided by the data store.

In an operation S102, the requesting device comprises at least one application capable to access data of data stores of a serving device or several different serving devices. The descriptor of the data store to be identified is determined in accordance with the applications capable to access data of the data stores to be identified. The descriptor is based for example on a description

associated with an application, on a description derived from the information supplied by an application or on a description associated with the kind of data processed by the application and provided via the data store(s). The designation kind of data relates to a data type which is to be understood as broad as possible, i.e. usually, types of data are described by an abstract description model which allows to identify different data content types such as a mime-type, a meta-type or any other data type descriptive formulation.

In accordance with data synchronization based on SyncML synchronization standard, the data type is employed as data store descriptor, wherein a MIME-type is used to associate with a certain application. For example, data of a calendar application is to be synchronized with calendar data stored in a central data store

In an operation S104, the identifying of the data store descriptor can be based on a user interaction. The user selects or defines the applications and/or the service in accordance to which one ore more data store are to be identified in order to be accessible. Moreover, the user may be allowed to select data type descriptors or data store descriptors out of a list presented to the user or enter manually such descriptors.

In an operation S106, a corresponding request is coded. The request instructs the request receiving device, here the data serving device, to look for one or more data store available to the serving device corresponding to the descriptor or descriptors contained in the request. Further, the request receiving device is instructed by the request to retransmit information relating to the one or more identified data store comprising at least an address information which allows applications executed on the requesting device to access the one or more identified data store.

The request structure is based on two structural part, a header part and a body part. The header part relates to common information such as identification of the request transmitting device, authentication information, user identification information, routing information, versioning information and the like. The body part is a container including one ore more instructional sequences to be parsed by the receiving device and to be executed in accordance therewith. For example, the body part comprises one or more sets of alert sequences each representing a matching set of instructions dedicated to a descriptor for instructing the receiving device to identify one or more matching data stores.

The operations S102, i.e. identifying applications or identifying data types and corresponding data store descriptors to be coded in the request, respectively, and the operation S106, i.e. generating or coding the request, respectively, can be performed subsequently or can be

performed iteratively.

5 In an operation S108, the generated request is transmitted to the request receiving device or the data serving device. The request receiving device can be specified, for example by a user input of an adequate device address information or alternatively may be pre-defined.

10 In an operation S110, the request receiving device or the data serving device receive the request, respectively, parses the request and operate in accordance with the instructional sequences comprised in the parsed request, i.e. the data serving device identifies data stores available to the requesting device and matching to the coded data store description or data type description which leads to one or more data stores providing data in accordance with the data type description. Or course, it is also possible that a corresponding data store is not available to the requesting device. In this case, the response comprises information according to the request informing the requesting device about the unavailability.

15 In an operation S112, the data serving device generates or codes a corresponding response, respectively, including information relating to the data store necessary to access the identified one or more data stores.

20 The operations S110 and S112 will be described in more detail with reference to Fig. 2 which illustrates an operations sequence of a request receiving device according to an embodiment of the invention.

25 In an operation S114, the requesting device receives the response, parses the received response and transmits the information relating to the identified data store(s) to the respective applications requiring configuration in accordance with the information relating to the identified data store(s) or configures directly the application(s) correspondingly.

30 In an operation S116, the applications of the requesting device capable to access data of the one or more identified data stores are configured in accordance with the information relating to the data store(s) comprised in the response.

In an operation S118, the configured applications are now informed about the data stores provided by data serving devices and the appropriated services can be established or used.

35 In an operation S200, the data store retrieval process illustrated above can be initiated by a plurality of preceding operation or processes. In the following a couple of initial processes is

illustratively described.

The data store retrieval process is manually initiated, i.e. a user initiates the process, e.g. if a certain application is to be configured or an existing configuration has to be adapted to meet new requirements.

The data store retrieval process is automatically initiate, e.g. at a first activation of the requesting device an automatic configuration is offered to a user of the device in order to configure included applications or similarly, a new application installed on the requesting device is detected and the automatic configuration is activated.

The data store retrieval process is initiated by a remote device. For example, the data serving device comprising one or more data stores providing data to the receiving device is reconfigured, wherein the reconfiguration affects the accessing devices, i.e. here the requesting device, a message is transmitted to the requesting device instructing the requesting device to generate the request such that the configuration of the applications affected by the reconfiguration of the data serving device meet the new requirements.

The data store retrieval process is initiated by a bootstrap message. A bootstrap message is used to transmit configuration information to a networking device at a first logging in to adapt configuration required applications to specific network properties. Mobile communication networks, especially cellular mobile communication networks, are able to employ bootstrap messages to configure network participating devices. Commonly, bootstrap messages are transmitted from the service provider operating the mobile communication network, preferably via a push mechanism.

It shall be noted, that in the aforementioned description of the operational sequence, it has been assumed that request receiving device and data serving device are the same devices. The presented operation can also be performed by communicating the request to a request receiving device having the capability and the information necessary to answer the request with an adapted response informing the requesting device of the actual data serving device being a separate device.

Fig. 3 shows a flow diagram illustrating an operational sequence for generating a response in reaction to a request, e.g. as illustrated in Fig. 1, according to an embodiment of the invention

In an operation S300, at receiving a request, the data store retrieval process is initiated.

In an operation S302, the request receiving device receives a request of the above stated kind. As described the request contain instructional sequences instructing the receiving device to identify certain services and/or data stores and to code and retransmit a response containing retrieved information relating to the identified services and/or data stores which allows to configure applications such that they can access the identified services and/or data stores.

In an operation S304, the request is parsed by the request receiving device or by a parsing application executed thereon, respectively. The parsing application further interprets the coded instructions causing to intimate adequate processes or to transmit data to processes capable to operate accordingly. The parsing, interpreting and executing in accordance with the instructions coded in the request may involve a plurality of applications which are interconnected via application program interfaces and cooperate with each other.

In an operation S306, a data store corresponding to the data store descriptor is identified. As aforementioned, the identification is based on the coded descriptor of the data store to be identified. For example, the descriptor of data stores and/or services is based on a descriptor of a data type associated to the data stored in the data store to be identified.

The identification of a data store in accordance with the coded descriptor can further take account of additional information included in the request. For example, a device identification or a user identification may allow to look up for data stores of restricted access, i.e. only certain devices or only a certain user or a certain group of users may be allowed to access a data store and the identification or retrieval process has consider such restrictions.

In an operation S308, information relating to the one or more identified data stores and the one or more identified services are determined or retrieved, respectively. For example, the retrieved information relate to necessary information such as an address information enabling access but also to further information such as access control information, access right information and the like.

In an operation S310, the gained information are coded in a response. The response comprises a response section to each instructional sequence in the request dedicated to a data store description for retrieval. In case of a successful retrieval process information relating to the data store is coded in the respective response section. In case of a unsuccessful retrieval process the respective response section contains information relating to the unavailability, which for example results in a disabling of an application of the requesting device to avoid processing failures of the

requesting device.

Analogously to the request, the response is structured in two structural parts, a header part and a body part. The header part relates to common information such as routing information, versioning information and the like. The body part is a container including one or more instructional sequences to be parsed by the receiving device and to be executed in accordance therewith. Here, the body part comprises several status information each representing a matching set of instructions each dedicated to a retrieval instruction set.

The operations S304, i.e. parsing and decoding the request, respectively, the operation S306, i.e. identifying at least one data store in accordance with the at least one descriptor and retrieving information relating to the at least one identified data store, and the operation S310, i.e. generating or coding the response, respectively, can be performed subsequently or can be performed iteratively.

In an operation S312, the response is re-transmitted to the requesting device.

The following figures present extracts of a request and a response corresponding to the request both based on and related to the SyncML synchronization standard extended by further adapted instructions. The SyncML meta-information is represented in a mark-up language. The meta-information is identifiable as a XML name space. The SyncML meta-information DTD (document type definition) defines the XML document type used to represent meta-information. The SyncML meta-information XML documents are specified using well-formed XML but not necessarily. The document type definition (DTD) makes heavy use of XML name spaces. Element types from the SyncML meta-information DTD can be used in other XML documents, including a SyncML message.

XML can be viewed as more verbose than alternative binary representations. This is often cited as a reason why it may not be appropriate for low bandwidth network protocols. In most cases, this DTD uses shortened element type and attribute names. This provides a minor reduction in verbosity. Additionally, the SyncML meta-information can be encoded in a tokenized, binary format.

Fig. 4 shows a request based on XML-coding in accordance with the SyncML synchronization standard according to an embodiment of the invention.

A line numbering and a subdividing of the presented code representing a request shall support

the following description of structural elements. Only relevant and invention related sections of illustrated request coding are described.

A code section CS1 refers to the introducing definition section of the request. A XML coding information, a character encoding and a SyncML versioning information is defined.

A code section CS2 relates to the header section of the request. The header section contains common information, here for example, the version of the document type description is defined on which the coding of request is based. The content of the header section is standardized by the SyncML synchronization Initiative and can be looked up in detail in public standard related documents.

A code section CS300 relates to the body section of the request. This code section will be described in detail with reference to further subsections included.

A subsection CS310 relates to an alert code section. Alert code section indicates a process to be initiated to the parsing device. Here, the alert code section contains an identification code 224 in line 11 instructing to initiate a data store retrieval process such as described with reference to Fig. 3. In accordance with the current SyncML synchronization standard, the alert code 224 is actually not assigned to any process.

A subsection CS311 comprised in the subsection CS310 contains the data store description, here a data type descriptor instructing the request receiving device to identify data store(s) contain/providing data in accordance with this data type descriptor. The data type is defined as a meta-type "text/x-vcard" associated with data relating to a vcard contact managing application.

A subsection CS320 relates to a further alert code section. Here, the alert code section also contains an identification code 224 in line 18 instructing to initiate a data store retrieval process such as described with reference to Fig. 3.

A subsection CS321 comprises in the subsection CS320 contains the data store description, here a data type descriptor instructing the request receiving device to identify data store(s) contain/providing data in accordance with this data type descriptor. The data type is defined as a MIME-type "text/x-vcal" associated with data relating to a vcal calendar application

Fig. 5 shows a response based on a modified XML-coding in accordance with the SyncML synchronization standard according to an embodiment of the invention.

A line numbering and a subdividing of the presented code representing a response shall support the following description of structural elements. Only relevant and invention related sections of illustrated response coding are described.

5 A code section CS4 refers to the introducing definition section of the response. A XML coding information, a character encoding and a SyncML versioning information is defined.

10 A code section CS5 relates to the header section of the response. The header section contains common information, here for example, the document type description is defined on which the coding of request is based. The content of the header section is standardized by the SyncML synchronization Initiative and can be looked up in detail in public standard related documents.

15 A code section CS600 relates to the body section of the response. This code section will be described in detail with reference to further subsections included.

20 A subsection CS610 comprises in the subsection CS600 relates to common status information related code section. The common status information includes in line 13 a base address information, designated as TargetRef, relating to the data serving device and effective to further address information comprised in the response and in line 14 an address information, designated as SourceRef, relating to the requesting device.

25 A subsection CS620 comprised in the subsection CS600 relates to status information corresponding to the first alert code section CS310 illustrated in Fig. 4. In accordance with the data type descriptor "text/x-vcard" included in code section C310 of the request, the response includes the corresponding data stores identified. A successful retrieving process is indicated by the code 200 in line 22. A code 415 contained in line 22 instead of the code 200 would indicate an unsuccessful retrieval process. The respective identified data stores or address information relating to the identified data stores are coded in following further subsections, respectively.

30 A subsection CS621 comprised in the subsection CS620 relates to a first identified data store or the address information relating to the first identified data store, respectively. The address information is coded as a relative address information relative to the base address information of included in subsection CS610, line 13. In accordance to the data type descriptor "text/x-vcard" a
35 corresponding data store address information "./Contact/PersonalContacts" has been retrieved and coded therein.

A subsection CS622 comprised in the subsection CS620 relates to a second identified data store or the address information relating to the second identified data store, respectively. The address information is coded as a relative address information relative to the base address information of included in subsection CS610, line 13. In accordance to the data type descriptor "text/x-vcard" a corresponding data store address information "./Contact/BusinessContacts" has been retrieved and coded therein.

The number of identified data stores codeable in the response request is not limited. Further subsection similar to the subsections CS621 or CS622 can be included in the subsection CS620.

A subsection CS630 comprises in the subsection CS600 relates to status information corresponding to the second alert code section CS320 illustrated in Fig. 4. In accordance with the data type descriptor "text/x-vcal" included in code section C320 of the request, the response includes the corresponding data stores identified. A successful retrieval process is indicated by the code 200 in line 39. A code 415 contained in line 39 instead of the code 200 would indicate an unsuccessful retrieval process. The respective identified data stores or address information relating to the identified data stores are coded in following further subsections, respectively.

A subsection CS631 comprised in the subsection CS630 relates to a first identified data store or the address information relating to the first identified data store, respectively. The address information is coded as a relative address information relative to the base address information included in subsection CS610, line 13. In accordance to the data type descriptor "text/x-vcal" a corresponding data store address information "./Contact/PersonalCalendar" has been retrieved and coded therein.

A subsection CS632 comprised in the subsection CS630 relates to a second identified data store or the address information relating to the second identified data store, respectively. The address information is coded as a relative address information relative to the base address information included in subsection CS610, line 13. In accordance to the data type descriptor "text/x-vcal" a corresponding data store address information "./Contact/BusinessCalendar" has been retrieved and coded therein.

The number of identified data stores codeable in the response request is not limited. Further subsection similar to the subsections CS631 or CS632 can be included in the subsection CS630.

The illustrated status information of subsections CS 620 and CS 630 corresponding to the data type descriptor included in the subsections CS310 and CS320 each comprise data store address

information. The status information are not limited to address information but can also include further information relating to the access requirements, access rights, data store preferences and properties and the like.

- 5 The illustrated address information are coded as uniform resource identifier. Further address information coding can be employed. For example, the coding can be based on uniform resource identifier and uniform resource name coding which may be also combined.

10 Fig. 6 illustrates components of a client device 30, i.e. aforementioned as requesting device, and a server device 20, i.e. aforementioned as request receiving or data serving device, respectively, for synchronization according to an embodiment of the invention.

15 A server device agent 220 represents a networked service that provides the possibility to exchange messages such as messages in accordance with the aforementioned request and response, respectively, with another counterpart client device agent 320. Further, the server device agent 220 and the client device agent 320 are capable and responsible for coding and/or decoding of the request and response, respectively. The server device agent 220 is hosted by the server 20 which may be a server device corresponding to the server device mentioned with reference to Fig. 1. Analogously, the client device agent 320 is hosted by the client 30 which may
20 be a client device corresponding to the client device mentioned with reference to Fig. 1.

The server 20 and client 30 are connected over a network. The network provides a logical communication connection between the server 20 and client 30, allowing the establishment of the end-to-end communication. A selection of logical connections and bearers thereof are
25 described in Fig. 1.

The client 30 may use the client device agent 320 to access the network and send messages to the server via the client adapter 340 and client interface 330, for example in accordance to the SyncML protocol standard. The client adapter 340 and the client interface 330 provides an
30 adaptation of the messages to be transmitted and/or to be received to the logical and physical requirements in accordance with the employed communication network. Correspondingly, the server 20, server device agent 220 and the server engine 210, respectively, receives or sends messages via the server adapter 240 and server interface 230 and manages the data stores 200 provided to the client 30 to be accessed. The server adapter 240 and the server interface 230
35 provides an adaptation of the messages to be transmitted and/or to be received to the logical and physical requirements in accordance with the employed communication network. Message

transmission operations are for example conceptually bound into a device frame, which is a conceptual frame for one or more required packages.

5 The client 20 has the ability by means of the client device agent 320 to code a data store retrieval request in view of the applications 300 operable with the device or the data types required by the applications 300. The server 20 is able by the means of the server device agent 220 to decode the request and by the means of the server device engine 210 to parse the received request, to operate the retrieval process in accordance with the instructions and one or more descriptors comprised in the request and finally to supply information to the server device agent 220 to code a
10 corresponding response basing on information relating to the data store(s) 200. The parsing and processing of the request may be executed by the server device engine 210 can be supported by a certain component specialized to identify one or more data stores in accordance with the descriptor and to retrieve information relating to the data store.

15 The response received by the client 30 is decoded by the means of the client device agent 320 and the decoding results are supplied to a configuration component 310 able to configure the applications 300 in accordance with the information relating to at least one data store decoded from the response request. The configuring component 310 can be supported by the client device agent 320 able to parse the received response and able to transmit only relevant processed
20 information to the configuration component 310.

The configured applications may employ the described client device interface 330 and client device adapter 340 to communicate to the data serving device comprising the one or more data stores. Here, the server device 20 comprises the data stores and communication with the data
25 stores may be performed through the server device adapter 240, the server device interface 230 and the server device engine 210 operating as a data store managing interface. Conveniently, the data stores to be accessed by the configured applications of the client device 30 may be provided by a dedicated separate serving device, i.e. separate from the depicted server device 20. Therefore, the server device 20 can comprise the necessary requested information to operated the
30 described methods or the server device 20 can retrieve the necessary requested information from the dedicated serving device.

The respective components necessary to operate the methods according to embodiments of the invention and designated to the client device and server device with reference to Fig. 5 have to be
35 implemented (also) within the particular device, i.e. the specific method related components of the client device in the server device and vice versa.

It shall be noted, that the implementation and the embodiments of the client device 30 and server device 20 is based on embodiments of synchronizing devices in accordance with the SyncML synchronization standard. Particularly, the basic operations of the server device engine 210, the server device agent 220 and the client device agent 320 are derived from these basic
5 embodiments. According to an embodiment of the present invention, these components being based on the SyncML synchronization standard have an improved functionality, i.e. the functionality in accordance with the SyncML synchronization standard and the functionality described with respect to the aforementioned methods according to embodiments of the invention and the aforementioned devices according to embodiments of the invention.

10 It will be obvious for those skilled in the art that as the technology advances, the inventive concept can be implemented in a different and broader number of ways. The invention and its embodiments are thus not limited to the examples described above but may vary within the scope of the claims.

Claims

1. Method for generating a request by a first device to retrieve information relating to at least one data store, characterized by
 - 5 - generating said request by including:
 - at least one data store descriptor suitable for characterizing said at least one data store; and
 - a command for instructing a second device to identify at least one data store matching with said at least one data store descriptor, to retrieve information relating to said at
10 least one identified data store and to return said retrieved information,
 - transmitting said generated request to said second device.
2. Method according to claim 1, characterized in that said generating comprises:
 - 15 - identifying said at least one data store descriptor to be coded.
3. Method according to any one of the preceding claims, characterized in that said at least one data store descriptor comprises at least one data type descriptor relating to at least one data content type.
- 20 4. Method according to claim 3, characterized in that said data type descriptor is a MIME content type definition.
5. Method according to any one of the preceding claims, characterized in that said information relating to said at least one data store includes an address information for accessing said at
25 least one data store.
6. Method according to any one of the preceding claims, wherein said request is based on the synchronization markup language (SyncML) protocol.
- 30 7. Method according to claim 6, characterized in that said command of said request is a modified ALERT command having a specific ALERT CODE and including a META element containing a TYPE element for defining said at least one data store descriptor.

8. Method for generating a response by a second device containing information relating to at least one data store in response to receiving a request for information of said at least one data store from a first device via a communication network, characterized by:
- identifying at least one data store matching with at least one data store descriptor included in said received request;
 - in case said at least one data store matches with said at least one data store descriptor: retrieving information relating to said at least one identified data store from said at least one identified data store;
 - in case no data store matches with said at least one data store descriptor: generating information relating to said at least one data store descriptor informing about said unsuccessfully matching;
 - generating said response including said information; and
 - transmitting said generated response to said first device.
9. Method according to claim 8, characterized in that said request is a request according to any one of the claims 1 to 7.
10. Method according to claim 8 or 9, characterized in that said at least one data store descriptor comprises at least one data type descriptor relating to at least one data content type.
11. Method according to any one of the claims 8 to 10, characterized in that said information relating to said at least one data store includes an address information for enabling said first device to access said at least one data store.
12. Method according to anyone of the claims 8 to 11, wherein said response is based on the synchronization markup language (SyncML) protocol.
13. Method according to claim 12, characterized in that said response includes at least one STATUS element including a SOURCE element including an address information of said at least one identified data store, wherein said address information is coded as a sequence including at least one of a uniform resource identifier (URI) and a uniform resource name (URN).

14. Software tool for handling data store related information, comprising program portions for carrying out the operations of any one of the claims 1 to 13, when said program is implemented in a computer program for being executed on a computer, a user terminal or a network device.

5

15. Computer program for handling data store related information, comprising program code sections for carrying out the operations of any one of the claims 1 to 13, when said computer program is executed on a computer, a user terminal or a network device.

10 16. Computer program product for handling data store related information, wherein said computer program product is comprising program code sections stored on a computer readable medium for carrying out the method of any one of the claims 1 to 13, when said computer program product is executed on a computer, a user terminal or a network device.

15 17. Device for generating a request to retrieve information relating to at least one data store, comprising:

- a request generating component for generating said request and
- a network interface for transmitting said request to a second device;

characterized in that said request generating component additionally comprises

- 20
- a component for including at least one data store descriptor into said request and
 - a component for including a command into said request, wherein said command is adapted for instructing said second device to identify at least one data store in accordance with said at least one data store descriptor, to retrieve information relating to said at least one identified data store and to return said retrieved information.

25

18. Device according to claim 17, wherein said device is adapted to perform the method according to any one of the claims 1 to 7.

19. Device for generating a response containing information relating to at least one data store in response to receiving a request for information of said at least one data store from a first device, comprising

30

- a network interface for receiving said request and for transmitting said response; and
- a response generating component for generating said response

characterized by

- a component for identifying at least one data store matching with at least one data store descriptor included in said received request;
- a component for retrieving information relating to said at least one identified data store;
- 5 and
- a component for including said retrieved information relating to said at least one identified data store, said component being comprised in said response generating component.

- 10 20. Device according to claim 19, wherein said device is adapted to perform the method according to any one of the claims 8 to 13.

Abstract

Networking devices require information relating to data stores, i.e. especially address information enabling the access of the networking devices to the serving device. Currently, such information about data stores is manually entered into the networking devices or the applications executed on the networking devices capable to access the data stores.

The present invention provides a method for generating a request for information about a data store. The request codes a data store descriptor which is used to characterize or identify a matching data store from a plurality of data stores. The re-transmitted information comprises retrieved information necessary for the requesting device or the applications executed thereon to access the identified data store, respectively. The present invention provides a method for generating a response in consequence on receiving a request for information about a data store. The data store descriptor coded in the request is used to characterize or identify a matching data store from a plurality of data stores and information about the data store is retrieved. This retrieved information coded in a response is transmitted to the previously requesting device enabling the requesting device or the applications executed thereon to access the identified data store, respectively.

20 ~~(Fig. 2)~~^A

A 20

1/6




Fig. 1

2/6




Fig. 2

3/6




Fig. 3

4/6




Fig. 4

5/6




Fig. 5

6/6




Fig. 6